



NOTE

1. PROVISION IS TO BE MADE FOR THE DISPOSAL OF WATER USED FOR IN PLACE TESTING OF COMPOUND METER EITHER THROUGH FLOOR DRAIN OR THE 125mm FERRULE.
2. IF HOT WATER TANK IS WITHIN 3.0m OF METER, THEN A CHECK VALVE IS REQUIRED BETWEEN THE METER AND HOT WATER TANKS.
3. FLANGED ENDS COMPLETE WITH TAPPED BLIND FLANGE.
4. BY-PASS MAY BE ONE PIPE SIZE SMALLER THAN METER SIZE AND MAY BE INSTALLED HORIZONTALLY.
5. WHERE METER ROOM IS NOT ADJACENT TO AN OUTSIDE WALL OR IS BELOW EXTERIOR FINISHED GRADE, THE CONTRACTOR/APPLICANT SHALL PROVIDE A CONTINUOUS E.M.T. CONDUIT COMPLETE WITH NYLON FISH LINE FROM METER ROOM TO 1000mm ABOVE EXTERIOR FINISHED GRADE.
6. WHERE REQUIRED, BACKFLOW PREVENTOR SHALL BE INSTALLED AFTER BOTH THE METER AND BY-PASS



**PUBLIC WORKS
STANDARD DRAWING**

REV. DATE: NOVEMBER 2011

APPROVED BY

DRAWN BY

A.L.

AINLEY GROUP

**50mm TRU-FLO COMPOUND METER
IN BUILDING**

STD. DWG. NUMBER

SCALE

1-4-18

N.T.S.