



Update on construction in your area

The Region of Peel is replacing aging watermain on Indian Grove as part of our maintenance program. The current watermain was installed in the 1950s and is at the end of its lifespan. A larger watermain that provides water to the Lorne Park area will also be installed along with the smaller (local) watermain on Indian Grove. The local watermain is on one side of the street with the larger watermain to follow on the opposite side of the street.

Completed work

- The local watermain has been installed on Indian Road, Indian Grove, and on South Sheridan Way to Tridom Court.
- The contractor flushed and connected the second half of the local watermain to the first half. The entire local watermain is now connected to the distribution system.
- Approximately half of the water services on Indian Grove have been transferred to the new watermain.



Copper water service with valve and anode to prevent corrosion.



Hydro vacuum excavation uses water and vacuum technology to safely excavate around more sensitive areas.

Coming up in the next two weeks

- The contractor will continue to transfer water services between 1456 Indian Grove and Tridom Court.
- **Important note:** Residents may be without water for approximately 15-30 minutes during this transfer and it is advised to run your water for a few minutes afterward to get any air out of the lines.
- Temporary restoration has begun on the southern end of Indian Grove.

Anticipated completion

- We are on schedule to complete most of the work (including all digging) by the end of 2021. Some restoration work (i.e. sod and landscaping) may need to be completed in Spring 2022.

Reducing the impact of construction

- We have put in a road closure on Indian Grove during construction. Residents will be allowed to access their properties, but no through traffic will be allowed.
- For everyone's safety, please avoid driving through the active construction area. Residents should access their property from the south end of Indian Grove if their property is south of the active construction area, and from the north end if their property is north of construction.
- We may need to block your driveway for a short time. We will contact you to arrange for the best time and for alternate access, if needed. Pedestrian access will always be maintained.

- We may need to temporarily shut off your water when connecting to the new watermain. It is our goal to let you know 48 hours (2 days) in advance if we need to do this. Occasionally, we may have to reduce this notice to 24 hours. We will do our best to notify you.
- If we must shut off your water because of an emergency, we will do everything we can to fix the problem as quickly as possible.
- We will let you know if there are any significant project changes.

In-ground sprinkler systems

- We recommend that you remove your sprinkler lines within 3 metres of the curb to avoid damage.
- Please email us if you would like to discuss your underground irrigation or sprinkler system outside your property line.

Did you know?

- Water distribution is done through a series of reservoirs (big holding tanks), underground pipes and pumping stations. The pumping stations pump the water through the pipes and into your home. Some of these pipes are 2.4m (8ft) in diameter, which means you could easily stand inside the pipe, even if you are very tall! The watermains we are installing on Indian Grove are 0.3m (1ft) and 0.6m (2ft) in diameter.

Questions or concerns?

- Visit the [project webpage](#) for ongoing updates
- Call 905-791-7800 extension 4409
- Email construction@peelregion.ca

[View the web version](#)

Accessible formats and communication supports are available upon request.



Region of Peel | 10 Peel Centre Drive, Brampton, Ontario L6T 4B9 Canada

[Unsubscribe](#)

[Update Profile](#) | [Our Privacy Policy](#) | [Customer Contact Data Notice](#)

Sent by construction@peelregion.ca