



**NOTES**

1. PLANTING SOIL MIXTURE SHALL CONFORM TO PEEL REGION SPECIFICATION FOR PREPARATION AND INSTALLATION OF TREE PLANTING SOIL.
2. SUBGRADE SOIL TO BE TILLED TO A DEPTH OF 25-50mm PRIOR TO INSTALLING PLANTING SOIL.
3. 25-50mm OF PLANTING SOIL SHALL BE PLACED IN THE TRENCH AND TILLED INTO THE SUBGRADE SOIL.
4. REMAINING PLANTING SOIL SHALL BE INSTALLED IN LIFTS OF 150mm-300mm AND COMPACTED BETWEEN 75% AND 80% OF MAXIMUM DRY DENSITY (PROCTOR).
5. TILL 40mm OF ORGANIC MATTER (COMPOST) INTO TOP LAYER OF INSTALLED PLANTING SOIL TO A DEPTH OF 60-90mm.
6. BOULEVARD SOIL TRENCH TO BE FINISHED WITH SOD IN ACCORDANCE WITH OPSS 803.
7. 150mm SUB DRAIN MAY BE REQUIRED DEPENDING ON LOCATION OF THE TREE, AT DIRECTION OF THE AGENCY, TO "T" OUTLET INTO EXISTING CATCH BASIN IN ACCORDANCE WITH OPSS 405.



**PUBLIC WORKS  
STANDARD DRAWING**

DATE: AUGUST 2016

APPROVED BY

DRAWN BY

G.K./B.N.

C.B.

STD. DWG. NUMBER

SCALE

**5-4-14**

N.T.S.

**BOULEVARD TREE PLANTING  
SOIL TRENCH FOR SOFTSCAPE BOULEVARDS  
(NEW CONSTRUCTION)**