

NOTES

- 1. MYCORRHIZAL INOCULANTS:
 - INSTALL MYKE PRO LANDSCAPE G.
- 2. WATERING:
 - SOAK THE ROOTBALL AND BACKFILL AREA WITH 20 LITRES OF WATER AFTER PLANTING.
- 3. ROOTBALL AND CONTAINER:
 - THE CONTAINER MUST BE REMOVED PRIOR TO PLANTING.
 - SHAVE OUTSIDE OF ROOTBALL TO REMOVE CIRCLING ROOTS IF PRESENT.
- 4. CROWN PRUNING:
 - PRUNE AT PLANTING TO CAREFULLY REMOVE DEAD, BROKEN, DISEASED OR DAMAGED BRANCHES.

Region of Peel	PUBLIC WORKS STANDARD DRAWING	DATE: AUGUST 2016	
Working for you		APPROVED BY	DRAWN BY
CONTAINER GROWN CONIFEROUS TREE PLANTING DETAIL ON SLOPE		G.K./B.N.	C.B.
		STD. DWG. NUMBER	SCALE
		5-4-8	N.T.S.