

Jacobs

Challenging today. Reinventing tomorrow.

Etobicoke Creek Trunk Sewer Improvements and Upgrades Schedule C Municipal Class Environmental Assessment

Online Public Engagement Public Information Centre #2 May 18, 2022 – June 1, 2022 Welcome!

Provide a project overview and explain why the project is being undertaken.

Provide details and seek input on the alternative solutions developed.

11111111

Provide information on the next stages of the project.

#### The Purpose of this Online Public Engagement is to:

Project Overview Receive Feedback

•







## **Project Overview: What, why and how?**



- The Etobicoke Creek Trunk Sanitary Sewers, from Kennedy Road to Derry Road in the City of Brampton, provides service to a large area extending north of Mayfield Road.
- Upgrades are required to address issues with the existing sanitary sewers and provide reliable sanitary service to future growth forecasted for the area.
- A Schedule 'C' Municipal Class Environmental Assessment (EA) Study is being undertaken to identify the preferred means to implement these upgrades.



# **Class Environmental Assessment Process**



Region

# **Class Environmental Assessment Process**

# Phase 1



Definition of the Problem or Opportunity



## **Problem Statement: Why are we doing this?**





- "A review of the condition and capacity of the existing Etobicoke Creek Trunk Sewer reveals that while the existing sewer is in relatively good condition with isolated areas requiring structural repair or operational and maintenance attention, repair or rehabilitation would not address the operational challenges posed by deep manholes, access limitations and proximity to Etobicoke Creek.
- The sewer is considered to be constrained conveying existing flows along approximately 28% of its length and would be unable to accommodate the growth forecasts developed in alignment with City of Brampton's growth plans."

# Phase 2



Identification and Assessment of Alternative Solutions and Selection of a Preferred Solution




# **Alternative Development Process: How do we arrive at a solution?**



Servicing Strategies	Long List of Concepts Alternatives	Review Relevant Studies	Short List of Viable Alternatives	Preliminary Preferred Alternative	Preferred Alternative
Pass/Fail Criteria Identify and screen servicing strategies to address the problem statement	Screening Level Assessment Identify and screen long list of servicing routes to achieve the strategy	Develop Criteria Conduct/Review relevant studies: - Natural Sciences - Hydrogeology - Geotechnical, - Stage 1 Archaeology - Cultural Heritage - Environmental Concerns	Detailed Triple Bottom Line+ Evaluation Evaluate short list of alternatives using detailed triple bottom line (TBL+) evaluation	Public, Indigenous, and Agency Review Consult and receive input to select the preferred alternative	Phase 2 Preferred Alignment
°	×			<b>ÁTATAA</b>	



#### **Phase 2: Short-List of Viable Alternatives**



# **Evaluation of Alternatives**




Category	Evaluation Criteria	Etobicoke Creek	CAA Lands	Kennedy Road	Deep Trunk	0 1
Technical Considerations	<ul> <li>Implementation Feasibility</li> <li>Permits and Approvals</li> <li>Reliability</li> <li>Effectiveness</li> <li>Compatibility with Existing Infrastructure</li> <li>Maximize Lifecyle Investment</li> <li>Flexibility</li> <li>Operational Accessibility</li> </ul>	0	O			Most Impacts/ Least Benefits Least Preferred Moderate Impacts/
Natural Environment	<ul> <li>Terrestrial Systems</li> <li>Aquatic Systems</li> <li>Soil Contamination</li> <li>Hydrogeology and Surface and Groundwater</li> <li>Soil, Bedrock and Geology</li> </ul>	0	O		O	Moderate Benefits Moderately Preferred
Socio-Cultural Environment	<ul> <li>Recreational Land Uses and Visual Landscape</li> <li>Future Planning Policies/Initiatives</li> <li>Disruption During Construction</li> <li>Archaeological and Cultural Resources</li> </ul>		0			Least Impacts/ Most Benefits Most Preferred
Economic Factors	<ul><li>Capital Cost</li><li>Operation and Maintenance</li></ul>		●	0	$\bullet$	hose released
Alternative Ranking		4	3	2	1	

# Phase 2 Preferred Alternative - Deep Trunk Alignment Considerations

12





# Phase 3




Identification and Assessment of Alternative Methods/Design Concepts and Selection of a Preferred Method/Design Concept



# What is the Relationship between Phase 2 and Phase 3?






# Design Concept Development Process: How do we arrive at a solution?



Preferred Construction Methods	Preliminary <b>Preferred</b> Construction Methods	Short List of Viable Construction Methods	Review Relevant Studies	Long List of Construction Methods	Construction Method Concepts
Phase 3 Preferred Design Concepts and Methods	Public, Indigenous, and Agency Review Consult and receive input to select the preferred design concept.	Detailed Triple Bottom Line + (TBL+) Evaluation Evaluate viability of short list of construction methods using detailed triple bottom line (TBL+) evaluation	Develop Criteria Conduct/Review relevant studies: - Cultural Heritage and Archaeological Assessment - Natural Features Technical Memorandum, - Geotechnical Investigations	Screening Level Assessment Identify the long list of construction methods and screen for feasibility (insert graphic –	Pass/Fail Identify construction method concepts and evaluate feasibility for the preferred alternative from Phase 2
				×	0

#### **Trunk Sewer Segments for Phase 3**






# **Construction Method Concepts**



Pass/ Fail

# Phase 3: Construction Method Concept – Open-Cut Construction Considerations





- Open-cut construction for the installation of infrastructure
- Allows for alignment to change direction as needed
- Disruptive to local area and environment
  - Impact traffic
  - Generate noise pollution and dust
  - Require larger area of land to dig
- Trenches deeper than 8 m are generally not feasible due to limitations in digging equipment

# Phase 3: Construction Method Concept – Tunneled Construction Considerations





- Installed below ground without the use of extensive trenches
- Cannot accommodate directional changes in alignment within a short distance
- Can generate vibration
- More expensive versus trenched construction
- Requires a minimum cover of twice the size of the tunnel

## **Phase 3: Construction Method Concepts – Pass/Fail**

#### Pass/Fail Criteria

- Depth of pipe:
  - Is the depth less than 8 m? → Best constructed by **Open-Cut**
  - or
  - Is the depth more than 8 m? → Best constructed by **Tunnel**
- Alignment:
  - Does it have multiple directional changes? → Best constructed by **Open-Cut**

Region

working with you

- or
- Is the alignment a straight alignment? → Best constructed by **Tunnel**

#### **Phase 3: Design Concepts – Pass/Fail**



	Tunneling Methods	Open Cut
Segment 1	~	×
Segment 2	~	×
Segment 3	$\checkmark$	$\checkmark$
Segment 4	×	~

Not FeasibleFeasible

21

# Long List of Construction Methods



**Screening Level Assessment** 

# **Phase 3: Long List of Tunneling Methodologies**



		Tunneling	Methods				
	Hand Mining	Drill and Blast	TBM	МТВМ			
Segment 1	×	×	~	~			
Segment 2	×	×	$\checkmark$	~			
Segment 3	×	×	×	~			
Segment 4	×	×	×	×			

Note: Hand Mining and Drill and Blast were eliminated from further analysis at the Screening Level Assessment due to length of segments, slow progress, health and safety concerns, geotechnical conditions, and disruptive nature of the methods

# **Review Relevant Studies**




**Develop Criteria** 

## **Phase 3: Tunneling Methodologies Preliminary Evaluation**



Category	Evaluation Criteria
Technical Considerations	<ul> <li>Tunnelling Considerations</li> <li>Geotechnical and Hydrogeological Conditions</li> <li>Property Requirements</li> <li>Accessibility</li> <li>Maintainability</li> <li>Schedule</li> </ul>
Natural Environment	<ul> <li>Terrestrial Environment</li> <li>Aquatic Environment</li> <li>Groundwater Impacts</li> <li>Contaminated Lands</li> <li>Soil Management</li> </ul>
Socio-Cultural Environment	<ul> <li>Impact to Cultural Heritage</li> <li>Archaeological Potential</li> <li>Impact to Recreation</li> </ul>
Economic Factors	Cost of Tunneling and Infrastructure

# **Short List of Viable Construction Methods**




**Detailed Triple Bottom Line + (TBL+) Evaluation** 

26




## **Phase 3: Tunneling Methodologies**

#### TBM





#### **MTBM**





#### Phase 3: Short List of Viable Design Methods - Segment 1





MTBM

## Phase 3: Short List of Viable Design Methods - Segment 2






#### Phase 3: Short List of Viable Design Methods – Segment 3









MTBM

#### Phase 3: Short List of Viable Design Methods - Segment 4







# Preliminary Preferred Design Methods

Public, Indigenous, and Agency Review

#### **Post-Evaluation Refinement**




Post-evaluation of construction methodologies, alignment was refined based on:

- Input from project stakeholders
- Natural environment investigations
- Avoidance of the natural environmental areas
- Technical limitations of the MTBM
- Site constraints

Evaluation results of construction methodologies

- Segment 1 MTBM
- Segment 2 MTBM
- Segment 3 MTBM
- Segment 4 Open-cut

## **Phase 3: Refined Preliminary Preferred Design Concept**




Region

addition of maintenance hole

35



#### **Phase 3: Refined Preliminary Preferred Design Concept Profile**



# What is a Tunnelling Shaft?





## **During Construction Shaft Location**





## **Post Construction Shaft Location**










#### Shaft Site Selection Criteria:

- Location defined by required connection to existing sewers
- · Proximity to Kennedy Road

- Proximity to trails
- Within natural environment
- Close (<50 m) to creek
- Within Area of Potential Environmental Concern
- · Permanent and temporary easements needed








#### Shaft Site Selection Criteria:

- Location defined by need to avoid the City of Brampton's cricket pitch
- Biscayne Connection avoids creek crossing

- Private property requirements
- Not easily accessible; will need temporary access during construction
- Within Area of Potential Environmental Concern
- Permanent and temporary easements needed









#### Shaft Site Selection Criteria:

- Location defined by opportunity to use property owned by Region of Peel
- Close to Westcreek Boulevard
- Allows for upstream and downstream microtunnel drives to be within typical ranges

- Within the natural environment
- Within Area of Potential Environmental Concern








#### Shaft Site Selection Criteria:

- Location defined by avoidance of wetland north of Tomken Road
- Avoids hydro towers
- Allows for typical drive lengths of MTBM **Constraints:**
- Within hydro corridor owned by IO/MTO/407 ETR Lands
- Within the natural environment
- Close in proximity (<50 m) to creek
- Within Area of Potential Environmental Concern
- · Permanent and temporary easements needed







#### **Shaft Site Selection Criteria:**

- Location defined by alignment's directional change
- Avoids crossing the existing sewers
- Within existing Region of Peel easement
- Mostly within City of Mississauga property

- Partially within private property during construction
- Will need a temporary paved road
- May impact one Cultural Heritage Resource
- Permanent and temporary easements needed





### Region of Peel working with you

#### **Shaft Site Selection Criteria:**

- Location defined by extent of open-cut segment
- Allows for trenchless crossing of Dixie Road
- Avoids crossing the existing sewers

- · Potential impact to accessing the baseball diamond
- Relatively close to creek (>50m)
- · Permanent and temporary easements needed



# Next Steps in Consultation and Engagement

Phase 4



Preparation of an Environmental Study Report DISCRETIONARY CONSULTATION

## How to Stay Connected and Involved



Phase 3	Phase 4		Phase 5	
	Document Study Outcomes in Environmental Study Report for Review and Comment		Initiate Field Investigations for Preferred Design	
May 2022	Summer 2022	September 2022	June 2022	December 2022
2nd Online Public Engagement to seek Impacts of Implementation		Issue Notice of Completion		Complete Preliminary Design



\*Feedback collected on this study will conform with the *Freedom of Information and Protection of Privacy Act*. It will be documented as part of this study and may be publicly available.

## How to Stay Connected and Involved?



Send your feedback or your questions on this project to the email below before June 1, 2022

## Italia Ponce, P.Eng.

Project Manager 10 Peel Centre Drive, 4<sup>th</sup> Floor, Suite A Brampton, ON, L6T 4B9 905-791-7800 Ext. 4583 Italia.ponce@peelregion.ca

- Environmental Study Report to be completed in late summer 2022
- If you would like to be kept updated on this project:
  - - https://www.peelregion.ca/pw/water/environassess/etobicoke-creek-sewer-imorovement.asp



https://twitter.com/peelpublicworks?lang=en



https://www.facebook.com/regionofpeel