



Welcome

Kennedy Road Sanitary Trunk Sewer Project

Public Information Centre #2

June 25, 2025

<https://peelregion.ca/construction/environmental-assessments/kennedy-road-sanitary-trunk-sewer-project>



About the Kennedy Road Sanitary Trunk Sewer Project



The existing trunk sewer system in Brampton does not have enough capacity to handle the expected increase in sewage from future growth.

Peel Region must increase sewer capacity by 2030 to support planned development in central Brampton and parts of Caledon.

To address this, Peel Region is planning to build a new large sanitary trunk sewer, between 1.5 and 2.1 metres in diameter. It will carry sewage from the area near Old School Road and Hurontario Street in Caledon to a new sewer being built on Kennedy Road in Brampton.

An additional connection is also needed at Queen Street. This will include extending a smaller 0.9 metre sewer pipe about 900 metres, from Kennedy Road to Rutherford Road North, to connect to the existing system.

In order to meet capacity demands by 2030, the construction will need to start in 2027. Construction will be coordinated, where possible, with other municipal infrastructure projects.




What is a Sanitary Trunk Sewer?

A large pipe that collects and moves wastewater by gravity from nearby and upstream areas to wastewater treatment plants. Designed to handle large volumes of wastewater, making them critical to maintaining public health and environmental quality.



Study Area

The Study Area is bounded by Old School Road to the north in the Town of Caledon and just south of Steeles Avenue to the south. Highway 410 forms the easterly border and Chinguacousy Road forms the westerly border of the Study Area.



Existing Trunks

- Etonicoke Creek
- Fletchers Creek

FLOW | Central Brampton

General Legend

- ▭ Kennedy Rd Study Area
- Sanitary Trunk Sewer Connection
- ▭ Municipal Boundary
- Roads
- Watercourse
- Waterbody

Data Sources:

Government of Ontario, Region of Peel
PN: 60736820
Jun, 09, 2025



Municipal Class EA Schedule C

Planning Process

Phases




Continuous Consultation & Engagement

What Have We Heard?

High level feedback themes we've heard and how the feedback has been considered:



Positive feedback from City of Brampton on the Flow | Central Brampton delivery approach and commitment to be an active partner.




Request to expand study area to capture future Hurontario Employment Secondary Plan area.



Peel Region Hurontario Employment Secondary Plan municipal water and wastewater infrastructure requirements are being confirmed as part of the current the 2025 Water and Wastewater Master Plan Update. Additionally, Peel Region has initiated a Water and Wastewater Program for South Caledon which will capture required infrastructure design and approvals for various water and wastewater projects.

Work Completed To Date



Water (Aquatics)

What we did:


- Assessed the condition of aquatic habitats.

What we found:

- 15 potential fish habitats, including one critical habitat for the Redside Dace fish species.

Why it matters:

- Although no in-water construction is planned, these watercourses and habitats need to be protected through mitigation measures based on Project design. Efforts will be made to avoid or minimize impacts.



Rivers and Streams (Fluvial Geomorphology)

What we did:

- Surveyed and assessed river and stream channels.

What we found:


- 14 river sections along the recommended preferred route, mapped erosion zones, and checked how deep pipes must be buried to avoid being exposed by erosion.

Why it matters:

- Improved understanding of river stability, now and in the future, and where erosion and sedimentation might occur.



Work Completed To Date



Land (Terrestrial)

What we did:

- Studied plants and wildlife, including habitats.

What we found:

- Some areas could be home to at-risk species, including several bats, birds and trees.

Why it matters:

- Construction works in these areas could pose harm to these species; special permits and mitigation measures will be required based on Project design. Efforts will be made to avoid or minimize impacts.



Archaeology (Stage 1 Assessment)

What we did:

- Took photos from the public road allowance to identify known and potential areas of archaeological potential or disturbance along or adjacent to the recommended preferred route.

What we found:

- Multiple locations along the recommended preferred route with high archaeological potential that have the potential to be impacted by the Project.

Why it matters:

- This work helps plan future archaeological work (Stage 2) and provides a roadmap for areas that require further archaeological assessment to identify potential unknown archaeological sites.



Cultural Heritage

What we did:

- Took photos from the public road allowance to identify known and potential built heritage resources and cultural heritage landscapes along or adjacent to the recommended preferred route.


What we found:

- Twelve important built heritage resources and cultural heritage landscapes were identified. Six of them have the potential to be impacted by the Project.

Why it matters:


- Efforts will be made to avoid or minimize impacts to built and cultural heritage resources. Mitigation measures have been suggested to reduce or avoid harm.

Upcoming Work




Traffic Impact Assessment

- Identifying impacts of lane closures and construction traffic on the road network through use of the City of Brampton travel demand model.
- Assessing localized impacts to individual intersections, temporary driveways and detours for large transport trucks / long-combination vehicles.



Subsurface Utility Engineering

- Locate underground utilities (e.g., storm sewers, sanitary sewers, watermain, power lines, internet cables) to help identify any conflicts with the proposed sewer.
- These will be important especially at shaft locations where surface digging will be required; shallow utilities are typically buried closer to the surface.



Geotechnical and Hydrogeology

- Borehole analysis along the Recommended Preferred Route alignment to understand soil / rock and groundwater conditions to inform the Project design phases.



Stage 2 Archaeology Assessment

- Test pit analysis to confirm or clear archaeological sites or material.
- This will help finalize shaft location.
- Typically, it is preferred to construct the shafts outside of areas where archaeological resources are present.


Alternative Solutions (Phase 2)

In this Phase of the EA process, we:

- Developed a routing evaluation methodology where we looked at the long list of alternatives to arrive at a short list for north and south routes (see next section of boards)
- Evaluated the short-listed routes using the information obtained from the technical studies and infrastructure analysis
- Selected a recommended preferred route for which design alternatives (e.g., construction methodology, shaft locations) will be considered in Phase 3.

Phase 1: Problem and Opportunity


Review background planning and policy documents, identify study area needs, problems and opportunities.



Phase 2: Alternative Solutions

Review existing environment, identify and evaluate feasible alternative sanitary sewer routing options, and identify short-list routing options. Evaluate short-list routing options and confirm preferred route.

Combined Short-listed South and North Routes



Shortlist Routes

— S1	— N1
— S2	— N2

FLOW | Central Brampton

General Legend


- Sanitary Trunk Sewer (STS) Connections
- ▬ Municipal Boundary
- Railway
- Roads
- Waterbody
- Watercourse

Data Sources:
Government of Ontario, Region of Peel
PN: 60736820
Jun, 19, 2025





Evaluation Method

An evaluation framework was created based on environmental components, as outlined the *Environmental Assessment Act*:






An evaluation of short-list routing options is complete. The routing options were rated based on their potential constraints relative to other routes, as follows:

-  Low Constraints (Preferred)
-  Medium Constraints (Less Preferred)
-  High Constraints (Least Preferred)

Recommended Preferred Route – South


- Route S1: Kennedy Road including Bovaird Drive
- Route S2: Kennedy Road including Vodden Street and Orangeville-Brampton Railway (OBR) Corridor Route, including a small section of Bovaird Drive
- Queen Street Sanitary Sewer Extension (common to S1 and S2): Queen Street from Rutherford Road North to Kennedy Road North
- Route S2: Kennedy Road including Vodden Street and Orangeville- Brampton Railway (OBR) Corridor Route is the recommended preferred south route, based on evaluation results.

Evaluation Category	Route S1: Kennedy/Bovaird	Route S2: Kennedy/Vodden/OBR
 Natural Environment		
 Socio-economic Environment		
 Cultural Environment		
 Legal / Jurisdictional		
 Technical		
 Climate Change		
 Economic / Financial		
		

Legend

 Preferred  Less Preferred  Least Preferred

Preferred overall in the south section




Shortlist Routes - South
S2
FLOW | Central Brampton

General Legend

- Sanitary Trunk Sewer (STS) Connections
- ▬ Municipal Boundary
- ▬ Railway
- ▬ Roads
- ▬ Waterbody
- ▬ Watercourse


Data Sources:
Government of Ontario, Region of Peel
PN: 60736820
Jun, 19, 2025



Recommended Preferred Route – North


- Route N1: Orangeville-Brampton Railway (OBR) Corridor including Old School Road Route
- Route N2: McLaughlin Road including Old School Road Route

Route N1: Orangeville-Brampton Railway (OBR) Corridor including Old School Road Route was selected as the recommended preferred south route based on the evaluation results.

Evaluation Category	Route N1: OBR/Old School Road	Route N2: McLaughlin/Old School Road
 Natural Environment		
 Socio-economic Environment		
 Cultural Environment		
 Legal / Jurisdictional		
 Technical		
 Climate Change		
 Economic / Financial		
Preferred overall in the north section 		

Legend

 Preferred  Less Preferred  Least Preferred




Shortlist Routes - North
N1
FLOW | Central Brampton

General Legend


- Sanitary Trunk Sewer (STS) Connections
- ▬ Municipal Boundary
- ▬ Railway
- ▬ Roads
- ▬ Waterbody
- ▬ Watercourse

Data Sources:
Government of Ontario, Region of Peel
PN: 60736820
Jun, 23, 2025



Recommended Preferred Route


The recommended preferred route is Route S2: Kennedy Road including Vodden Street and Orangeville-Brampton Railway (OBR) Corridor and Route N1: Orangeville-Brampton Railway (OBR) Corridor including Old School Road to Hurontario Street.



Alternative Design Concepts (Phase 3)

Phase 3 of the EA process involves considerations to the following alternative design construction methodologies based on the recommended preferred route identified in Phase 2:


- **Methods of construction:** The following boards describe different methods of construction and preliminary evaluation results. As a first step, profile drawings were created to confirm the required depth of the new sewer. This analysis concluded that the new sewer will need to be between 15 to 30 metres deep, which would be very difficult to construct by the open-cut method based on built-up environment and available road right-of-way width. Therefore, trenchless construction was determined to be the preferred method.
- **Preliminary shaft locations:** From a planning and risk mitigation perspective, all viable potential shaft locations have been identified based on the methodology requiring the most shafts in mind (microtunneling), with shafts being spaced approximately 800 metres apart due to the preliminary machine sizes. Each shaft location requires space to set up equipment for staging and operation. All efforts will be made to maximize right-of-ways and reduce easement needs.
- **Construction impacts and mitigation measures:** Based on the preliminary preferred construction methodology and shaft locations, construction impacts (e.g., tree removals, disruption to vehicular, transit and active transportation) have been identified along with preliminary mitigation measures that will be refined during the subsequent design phases.



Construction Methods – Open-cut vs. Trenchless

Open-cut

Construction methodology where a trench is cut into the ground for the installation of the sewer pipe and maintenance holes. All disturbed areas are returned to existing conditions.




Trenchless

Construction methodology used to install the sewer pipe with minimal surface excavation, except at shaft locations. Shafts are needed to lower or retrieve the tunneling machinery. Shafts can be used for the construction of maintenance holes. All disturbed areas are returned to existing conditions.


Construction Methods – Preliminary Evaluation of Open-cut vs. Trenchless

Open-Cut	Trenchless
Significant traffic disruptions due to open cut trenching in road right-of-ways	Minimizes surface disruption and traffic impacts, especially in urban corridors ✓
Very challenging to construct considering sewer depths ranging 10-20m below ground	Safer and more practical for deep installations (e.g., 10-20m pipe depths) ✓
Higher groundwater management required due to larger surface impacts	Reduced groundwater management as impacts are limited to shaft locations ✓
More excavated materials to manage due to much larger surface impacts	Less contaminated soil to handle as impacts are limited to shaft locations ✓
Longer timeline to construct	Shorter timeline to construct ✓
	Preferred


What is a...



Compound: The fenced area where construction will take place. Each compound will require a staging area where construction equipment can be stored and excavated material can be brought to the surface for disposal (i.e., hauled away in trucks). Once tunnelling operations are completed, the staging area will be restored to original condition or better.




Shaft: A deep hole providing access to underground tunnels where work takes place. The shaft is always inside a compound.



Compound site



Placing pipe down a shaft*




Bird's eye view of shaft*

*Photo credit: Peel's Burnhamthorpe Water Project;
Consultant: Hatch Ltd

Construction Methods – Tunnel Boring Machine vs. Microtunneling

Tunnel Boring Machine

This is a type of trenchless tunneling methodology, using a large boring machine. These are typically large in diameter and can tunnel long distances, enabling shafts to be spaced further apart. They are operated by an operator underground.



Microtunneling


Trenchless tunneling methodology, using a micro-tunnel boring machine (MTBM). MTBMs are typically smaller, and tunnel shorter distances, requiring shorter spaced shafts. They are operated from control containers located above ground.

Construction Methods – Preliminary Evaluation of Tunnel Boring Machine vs. Microtunneling

Tunnel Boring Machine	Microtunneling*
More grouting between tunnel and pipe as TBMs are much larger than the pipe size identified for this project.	Less grouting between tunnel and pipe as MTBMs are available in a range of smaller sizes, closer to the pipe size needed for this project. ✓
Needs man-entry and tunnel ventilation	No need for man-entry. Safer, remotely operated from the surface ✓
Larger shaft footprint – more difficult to install	Smaller shaft footprint – easier to install in tight urban locations ✓
Results in fewer shaft compounds due to longer tunnel drives ✓	Requires greater number of shaft compounds due to shorter tunnel drives
Larger minimum diameter tunnel results in more spoil to manage	Generates less spoil ✓
Less maneuverability for alignment changes	Better alignment control in constrained areas ✓
Greater volume of excavation can increase settlement risks if not carefully managed	Reduced risk of surface settlement: Pressure-balanced excavation method ✓
Longer timeline to construct and more costly	Shorter timeline to construct and less costly ✓
Preferred	

*Note:
microtunneling
may not be a
preferred option
for other projects.

Potential Shaft Locations



Preliminary Shaft Locations

FLOW | Central Brampton

General Legend


- Recommended Preferred Route
- Municipal Boundary
- + Railway
- Roads
- ~ Watercourse
- Waterbody

Data Sources:

Government of Ontario, Region of Peel
PN: 60736820
Jun, 19, 2025



Managing Construction Impacts




Water Crossings and Connections including Floodplain Management:

- Use trenchless technology at watercourse crossings where applicable
- Follow MNRF fisheries construction timing windows where applicable
- Connections to existing sanitary trunk sewers will avoid in-water works
- Follow erosion / sedimentation control strategy
- Restore disturbed areas to natural or better conditions



Trees and Vegetation:

- Minimize tree and vegetation removal
- Prepare Tree Protection Plan
- Compensate for lost trees




Contaminated Soils Through Spills:

- Soil contamination mitigation strategies will address any risks with contaminated soil and groundwater.
- Ensure proper handling / maintenance of construction equipment
- Prepare and follow contingency plans for control and cleanup should a spill occur



Noise/Vibration/Dust:

- Restrict high noise construction activities to day shift where required
- Adhere to noise by-laws where possible
- Complete preconstruction building structure surveys
- Dust control by spraying water / street sweeping
- Fence/hoarding of construction site along property limits and access roadway



Groundwater Management:


- Minimize dewatering
- Implement dewatering plan based on hydrogeological assessment



Traffic Management and Access:

- Prepare Traffic Management Plan
- Minimize access disruption
- Provide alternate pedestrian access
- Provide advanced notification

Project Progress and Next Steps



Stay Connected

Fill out the online
survey by
July 9, 2025:



Sign up for the mailing list or send any feedback,
questions or concerns to:

Italia Ponce, P. Eng.,
Project Manager, Peel Region
italia.ponce@Peelregion.ca

Faranak Amirsalari, MES, MCIP, RPP
Environmental Planner, AECOM
Faranak.Amirsalari@aecom.com

Please view the Kennedy Road Sanitary Trunk Sewer Project website for more
information, and to stay up to date: